

MAR 9 1939

U. S. DEPARTMENT OF COMMERCE

**BUILDING
MATERIALS
AND
STRUCTURES**

REPORT BMS12

Structural Properties of "Steelox"
Constructions for Walls,
Partitions, Floors, and Roofs
Sponsored by Steel
Buildings, Inc.

by

HERBERT L. WHITTEMORE

AMBROSE H. STANG, *and*

VINCENT B. PHELAN



NATIONAL
BUREAU OF STANDARDS



The program of research on building materials and structures undertaken by the National Bureau of Standards is planned with the assistance of the following advisory committee designated by the Subcommittee on Design and Construction of the Central Housing Committee.

TECHNICAL RESEARCH GROUP

WALTER JUNGE, Federal Housing Administration, *Chairman*

A. C. SHIRE, United States Housing Authority, *Vice Chairman*.

A. G. BEAR,
Veterans' Administration.
PIERRE BLOUKE,
Home Owners' Loan Corporation.
C. W. CHAMBERLAIN,
Procurement Division.
JOS. M. DALLAVALLE,
Public Health Service.
HUGH L. DRYDEN,
National Bureau of Standards.
G. E. KNOX,
Bureau of Yards and Docks,
Navy Department.

CHARLES E. MAYETTE,
United States Housing Authority.
VINCENT B. PHELAN,
National Bureau of Standards.
E. A. POYNTON,
Office of Indian Affairs.
JOHN H. SCHAEFER,
Procurement Division.
GEORGE W. TRAYER,
United States Forest Service.
ELSMERE J. WALTERS,
Quartermaster Corps, War Department.

STERLING R. MARCH, *Secretary*.

The program is administered and coordinated by the following staff committee of the Bureau:

HUGH L. DRYDEN, *Chairman*

P. H. BATES
H. C. DICKINSON

W. E. EMLEY
G. E. F. LUNDELL

A. S. McALLISTER
H. S. RAWDON

The Forest Products Laboratory of the United States Department of Agriculture is cooperating with the National Bureau of Standards in studies of wood constructions.

How To Purchase

BUILDING MATERIALS AND STRUCTURES REPORTS

On request, the Superintendent of Documents, U. S. Government Printing Office, Washington, D. C., will place your name on a special mailing list to receive notices of new reports in this series as soon as they are issued. There will be no charge for receiving such notices.

An alternative method is to deposit with the Superintendent of Documents the sum of \$5.00, with the request that the reports be sent to you as soon as issued, and that the cost thereof be charged against your deposit. This will provide for the mailing of the publications without delay. You will be notified when the amount of your deposit has become exhausted.

If 100 copies or more of any report are ordered at one time, a discount of 25 percent is allowed.

Send all orders and remittances to the *Superintendent of Documents, U. S. Government Printing Office, Washington, D. C.*

UNITED STATES DEPARTMENT OF COMMERCE · Harry L. Hopkins, Secretary

NATIONAL BUREAU OF STANDARDS · Lyman J. Briggs, Director

BUILDING MATERIALS *and* STRUCTURES

REPORT BMS12

Structural Properties of "Steelox"
Constructions for Walls, Partitions,
Floors, and Roofs Sponsored by
Steel Buildings, Inc.

by HERBERT L. WHITTEMORE, AMBROSE H. STANG,
and VINCENT B. PHELAN



ISSUED FEBRUARY 1, 1939

The National Bureau of Standards is a fact-finding organization; it does not "approve" any particular material or method of construction. The technical findings in this series of reports are to be construed accordingly.

UNITED STATES GOVERNMENT PRINTING OFFICE · WASHINGTON · 1939

FOR SALE BY THE SUPERINTENDENT OF DOCUMENTS, WASHINGTON, D. C. · PRICE 15 CENTS

Foreword

THIS REPORT is one of a series issued by the National Bureau of Standards on the structural properties of constructions intended for low-cost houses and apartments. Practically all of these constructions were sponsored by groups within the building industry which advocate and promote the use of such constructions and which have built and submitted representative specimens as outlined in report BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions. The sponsor is responsible for the representative character of the specimens and for the detailed description given in each report. The Bureau is responsible for the accuracy of the test data.

This report covers only the load-deformation relations and strength of the structural elements submitted when subjected to compressive, transverse, concentrated, impact, and racking loads by standardized methods simulating the loads to which the elements would be subjected in actual service. It may be feasible to determine later the heat transmission at ordinary temperatures and the fire resistance of these same constructions and perhaps other properties.

The National Bureau of Standards does not "approve" a construction, nor does it express an opinion as to the merits of a construction for reasons given in reports BMS1 and BMS2. The technical facts on these and other constructions provide the basic data from which architects and engineers can determine whether a construction meets desired performance requirements.

LYMAN J. BRIGGS, *Director.*

Structural Properties of "Steelox" Constructions for Walls, Partitions, Floors, and Roofs Sponsored by Steel Buildings, Inc.

by HERBERT L. WHITEMORE, AMBROSE H. STANG, and VINCENT B. PHELAN

CONTENTS

	Page		Page
Foreword.....	ii	V. Partition <i>AM</i> —Continued.	
I. Introduction.....	1	2. Impact load.....	11
II. Sponsor and product.....	2	3. Concentrated load.....	11
III. Specimens and tests.....	2	VI. Floor <i>AN</i>	12
IV. Wall <i>AL</i>	3	1. Sponsor's statement.....	12
1. Sponsor's statement.....	3	(a) Materials.....	12
(a) Materials.....	3	(b) Description.....	12
(b) Description.....	4	(c) Comments.....	13
(1) Four-foot wall specimens.....	4	2. Transverse load.....	13
(2) Eight-foot wall specimens.....	6	3. Concentrated load.....	13
(c) Comments.....	6	4. Impact load.....	14
2. Compressive load.....	7	VII. Roof <i>AO</i>	14
3. Transverse load.....	7	1. Sponsor's statement.....	14
4. Concentrated load.....	7	(a) Materials.....	14
5. Impact load.....	9	(b) Description.....	15
6. Racking load.....	10	(c) Comments.....	16
V. Partition <i>AM</i>	10	2. Transverse load.....	16
1. Sponsor's statement.....	10	3. Concentrated load.....	17
(a) Materials.....	10	VIII. Additional comments by sponsor.....	17
(b) Description.....	10	IX. Selected references.....	17

ABSTRACT

FOR THE PROGRAM on the determination of the structural properties of low-cost house constructions, Steel Buildings, Inc. submitted 30 specimens representing their "Steelox" constructions for walls, partitions, floors, and roofs.

The wall specimens were subjected to compressive, transverse, concentrated, impact, and racking loads; the partition specimens to impact and concentrated loads; the floor specimens to transverse, concentrated, and impact loads; and the roof specimens to transverse and concentrated loads. The transverse, concentrated, and impact loads were applied to both faces of wall specimens. For each of these loads three like specimens were tested. The deformation under load and the set after the load was removed were measured for uniform increments of load up to the maximum load, except for concentrated loads, for which the set only was determined. The results are presented graphically and in tables.

I. INTRODUCTION

IN ORDER to provide technical facts on the performance of constructions which might be used in low-cost houses, to discover promising constructions, and ultimately to determine the properties necessary for acceptable performance, the National Bureau of Standards has invited the building industry to cooperate in a program of research on building materials and structures for use in low-cost houses and apartments. The objectives of this program are described in report BMS1, Research on Building Materials and Structures for Use in Low-Cost Housing,¹ and that part of the program relating to structural properties in report BMS2, Methods of

¹ Price 10 cents. See cover page II.

Determining the Structural Properties of Low-Cost House Constructions.²

As a part of the research on structural properties, six masonry wall constructions have been subjected to a series of standardized laboratory tests to provide data on the properties of some constructions for which the behavior in service is generally known. These data are given in report BMS5, Structural Properties of Six Masonry Wall Constructions.³ Similar tests have been made on wood-frame constructions by the Forest Products Laboratory of the United States Department of Agriculture, the results of which will be given in a subsequent report in this series.

This report describes the structural properties of constructions sponsored by one of the manufacturers in the building industry. The specimens were subjected to compressive, transverse, concentrated, impact, and racking loads, simulating loads to which the elements of a house are subjected. In actual service, compressive loads on a wall are produced by the weight of the roof, second floor and second-story walls if any, furniture, and snow and wind loads on the roof. Transverse loads on a wall are produced by the wind, concentrated and impact loads by furniture or accidental contact with heavy objects, and racking loads by the action of the wind on adjoining walls. For nonload-bearing partitions, impact loads may be applied accidentally by furniture or by a person falling against the partition, and concentrated loads by furniture or by a ladder or other object leaning against the partition. Transverse loads are applied to floors by furniture and by the occupants; concentrated loads by furniture, for example, the legs of a piano; and impact loads by objects falling on the floor or by persons jumping on the floor. Transverse loads are applied to roofs by wind and snow; concentrated loads, by persons walking on the roof, and by tools and equipment when the roof is constructed or repaired.

The deflection and set under each increment of load were determined except for concentrated loads. For some of the newer constructions the deflection and set are important when judging whether the construction will be satisfactory in a house under service conditions.

² Price 10 cents.

³ Price 15 cents.

II. SPONSOR AND PRODUCT

THE SPECIMENS were submitted by Steel Buildings, Inc., Middletown, Ohio, and represented constructions sold under the trade name "Steelox." The load-bearing wall, floor, and roof constructions consisted essentially of interlocking, channel-shaped, sheet-steel panels. The nonload-bearing partition was of conventional wood-frame construction.

III. SPECIMENS AND TESTS

THE SPECIMENS represented four elements of a house which were assigned the following symbols: Wall, *AL*; partition, *AM*; floor, *AN*; and roof, *AO*. The specimens were assigned designations in accordance with table 1.

TABLE 1.—*Specimen designations*

Element	Construction symbol	Specimen designation	Load	Load applied
Wall.....	<i>AL</i>	<i>C1, C2, C3</i>	Compressive..	Upper end.
Do.....	<i>AL</i>	<i>T1, T2, T3</i>	Transverse....	Inside face.
Do.....	<i>AL</i>	<i>T4, T5, T6</i>	do.....	Outside face.
Do.....	<i>AL</i>	<i>P1, P2, P3^a</i>	Concentrated..	Inside face.
Do.....	<i>AL</i>	<i>P4, P5, P6^a</i>	do.....	Outside face.
Do.....	<i>AL</i>	<i>I1, I2, I3</i>	Impact.....	Inside face.
Do.....	<i>AL</i>	<i>I4, I5, I6</i>	do.....	Outside face.
Do.....	<i>AL</i>	<i>R1, R2, R3</i>	Racking.....	Upper end.
Partition.....	<i>AM</i>	<i>I1, I2, I3</i>	Impact.....	Either face.
Do.....	<i>AM</i>	<i>P1, P2, P3^a</i>	Concentrated..	Do.
Floor.....	<i>AN</i>	<i>T1, T2, T3</i>	Transverse....	Upper face.
Do.....	<i>AN</i>	<i>P1, P2, P3^a</i>	Concentrated..	Do.
Do.....	<i>AN</i>	<i>I1, I2, I3</i>	Impact.....	Do.
Roof.....	<i>AO</i>	<i>T1, T2, T3</i>	Transverse....	Do.
Do.....	<i>AO</i>	<i>P1, P2, P3^a</i>	Concentrated..	Do.

^a These specimens were undamaged portions of the specimens used in the transverse or impact tests.

The specimens were tested in accordance with BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions,⁴ which also gives the requirements for the specimens and for determining the price. For the transverse specimens the deflection was measured with two taut-wire mirror-scale deflectometers, one on each edge, instead of with the deflection-measuring frame and dial micrometers.

The tests were begun January 3, 1938, and completed January 12, 1938. The sponsor's representative witnessed the tests.

⁴ Price 10 cents.

IV. WALL AL

1. SPONSOR'S STATEMENT

(a) Materials

Steel.—Hot-rolled sheets, hot-dip galvanized and prepared for paint by the "Paint Grip" process. The chemical composition of the steel is given in table 2 and the average mechanical properties in table 3. American Rolling Mill Co.'s "Armco."

TABLE 2.—Chemical composition of the steel

Element	Content	
	Minimum	Maximum
	Percent	Percent
Carbon.....	0.05	0.10
Manganese.....	.25	.35
Phosphorus.....		.05
Sulfur.....		.05

TABLE 3.—Average mechanical properties of the steel

Gage number, United States Standard	Approximate thickness	Direction	Yield point	Tensile strength	Elongation in 2 in.
	in.		lb/in. ²	lb/in. ²	Per- cent
20	0.0363	In direction of rolling.....	26,000	40,000	32
		Across direction of rolling.....	29,500	44,000	29
18	.049	In direction of rolling.....	27,000	41,000	32
		Across direction of rolling.....	30,000	45,000	29
12	.1072	In direction of rolling.....	33,000	46,000	39
		Across direction of rolling.....	34,000	47,000	39

The sheets were galvanized with Prime Western zinc complying with ASTM Standard B6-37 and having a maximum of 1.60 percent of lead and 0.08 percent of iron. The weight of the zinc coating was 1.25 to 1.50 oz/ft² for the 18- and 20-gage sheets and 1.75 to 2.00 oz/ft² for the 12-gage sheets.

The galvanized sheets were prepared for paint by the "Paint Grip" process according to the following specification:

"All galvanized sheets and members shall be phosphated by immersion in a solution containing free phosphoric acid, an oxidizing agent (nitrate), and iron and zinc phosphate. After this treatment the articles shall be thoroughly rinsed in clear water."

Hook bolts.—Special, $\frac{3}{8}$ -in. diam, 16 threads per in., 1½ in. long, with $\frac{1}{16}$ -in. hook, made from

SAE 1035 cold-drawn steel, not heat-treated; with standard wrought-steel washers, and hexagonal steel nuts, cold-punched and trimmed, single chamfer and countersink. Bolts, nuts, and washers were plated with cadmium not less than 0.0002 in. thick. Lamson & Sessions Co.

Screws.—Self-tapping, $\frac{3}{4}$ in., No. 10 (0.190-in. diam), 13 threads per in., round head, hardened and plated with cadmium about 0.00035 in. thick. Parker-Kalon Corporation's "Type A."

Asphalt emulsion.—Brushing consistency. The formula is given in table 4. Armstrong Paint and Varnish Works' "XA-1696."

TABLE 4.—Formula for asphalt emulsion "XA-1696"

Ingredient	Content, water-free basis	
	Minimum	Maximum
	Percent	Percent
Bentonite clay.....	4	4.5
Asphalt.....	93	
Asbestos fiber.....	1.5	2
Rust inhibitor.....		1

Asphalt.—Softening point 180° F. Logan-Long Co.

Felt.—Rag base, saturated with asphalt; weight, 65 lb/108 ft² (Asphalt roofing). Philip Carey Co.

Adhesive.—The formula is given in table 5. Armstrong Paint and Varnish Works' "No. 106-V."

TABLE 5.—Formula for adhesive "No. 106-V"

Ingredient	Content
	Percent
Parolite.....	38
Gilsonite.....	12.9
Flux asphalt.....	10.2
Kerosene.....	38.9
	100.0

Wood.—Pine, shortleaf, yellow, No. 1 common, finished four sides.

Screw nails.—Heavy-duty, 1½ in. long, No. 6, 8 threads per in., quadruple thread, flat head, needle point, made from SAE 1315 (high side) steel, water-quenched from 1,750° F, and plated with cadmium about 0.0001 in. thick. Hillwood Manufacturing Co.'s "Helyx Drive Screw Nails."

'Insulating board.—Wood-fiber. Insulite Co.'s 'Graylite Building Board.'

Finishing nails.—6d, 2 in. long.

Paint.

Casein, priming. United States Gypsum Co.'s "K-Cemo."

Casein, finish. United States Gypsum Co.'s "Texolite."

Oil, priming, blue lead. Armstrong Paint and Varnish Works' "No. 1506."

Oil, undercoating, white. Armstrong Paint and Varnish Works' "XA 2140."

Oil, finish, white. Armstrong Paint and Varnish Works' "No. 1555."

The formulas for the oil paints are given in tables 6, 7, and 8.

TABLE 6.—Formula for blue-lead paint "No. 1506"

Paint		Pigment		Vehicle	
Ingredient	Content, by weight	Ingredient	Content, by weight	Ingredient	Content, by weight
	Percent		Percent		Percent
Pigment.....	57.24	Sublimed blue lead.....	69.88	Boiled linseed oil.....	96.47
Vehicle.....	42.76	Zinc oxide.....	30.12	Mineral spirits.....	3.53
	100.00		100.00		100.00

TABLE 7.—Formula for white undercoating paint "XA 2140"

Paint		Pigment		Vehicle	
Ingredient	Content, by weight	Ingredient	Content, by weight	Ingredient	Content, by weight
	Percent		Percent		Percent
Pigment.....	64.94	Lead carbonate.....	25.02	Raw linseed oil.....	35.79
Vehicle.....	35.06	Titanium dioxide.....	29.54	Spar varnish.....	34.23
	100.00	Silica and silicates.....	45.44	Cobalt drier.....	2.60
			100.00	Mineral spirits.....	27.38
					100.00

TABLE 8.—Formula for white finish paint "No. 1555"

Paint		Pigment		Vehicle	
Ingredient	Content, by weight	Ingredient	Content, by weight	Ingredient	Content, by weight
	Percent		Percent		Percent
Pigment.....	64.70	Lead carbonate.....	59.35	Refined linseed oil.....	96.32
Vehicle.....	35.30	Zinc oxide.....	15.92	Heat-treated linseed oil.....	3.40
		Titanium dioxide.....	4.64	Zinc drier.....	0.12
		Barium sulfate.....	4.64	Lead drier.....	.08
		Silica and silicates.....	15.45	Manganese drier.....	.08
	100.00		100.00		100.00

(b) Description

(1) *Four-Foot Wall Specimens.*—The 4-ft wall specimens were 8 ft 0 in. high, 4 ft 0 in. wide, and 4½ in. thick. Each specimen consisted of three interlocked sheet-steel "Steelox" panels, *A*, as shown in figures 1 and 2, fastened to a sheet-steel sill, *B*, at the lower end, and to a sheet-steel wall plate, *C*, and a sheet-steel angle, *D*, at

the upper end, by hook bolts. One flange of the wall plate was also fastened to the panels by screws. The panels formed the outside face and studs. The sides of the flanges of the panels which were in contact after assembly were covered with oil priming paint applied with a brush before assembly. The inside of the assembled panels, sill, and plate was covered with one coat of asphalt emulsion applied with a

brush, and the lower end was sealed with asphalt, $\frac{1}{2}$ in. thick. The bottom of the sill was covered with a strip of felt fastened by adhesive. Horizontal wood furring strips, *E*, were fastened to the studs by screw nails and an insulating-board inside face, *F*, was fastened to the furring strips by finishing nails. The inside face was covered with one coat of casein priming paint and one coat of casein finish paint. The outside face was covered with two coats of oil undercoating paint and one coat of oil finish paint.

The price of this construction was \$0.52/ft².

Panels.—The panels, *A*, were channels, 1 ft 4 in. by 3 in., 7 ft 11 $\frac{3}{4}$ in. long, formed from stretcher-leveled and resquared sheet steel, No. 20 United States Standard Gage (0.0368 in. thick before galvanizing). The edges of the




FIGURE 1.—Four-foot wall specimen AL.

A, panel; *B*, sill; *C*, wall plate; *D*, angle; *E*, furring strip; *F*, inside face.

flanges of each panel were formed to interlock with the flanges of adjacent panels. The flanges when interlocked formed studs of two thicknesses of steel, integral with the outside face.

Sill.—The sill, *B*, was an angle, 3 $\frac{3}{4}$ by 2 $\frac{1}{2}$ in., 4 ft 1 in. long, formed from sheet steel, No. 12 United States Standard Gage (0.1072 in. thick before galvanizing). The horizontal 3 $\frac{3}{4}$ -in. leg had holes for $\frac{1}{2}$ -in. anchor bolts, spaced 1 ft 4 in. on centers. The vertical leg had slots, 2 $\frac{7}{8}$ by $\frac{3}{8}$ in., spaced 5 in. on centers, in two rows, spaced $\frac{3}{4}$ in. The slots were staggered and overlapped $\frac{3}{8}$ in. The panels were fastened to the sill by hook bolts which passed through the slots and engaged the studs.

Wall plate.—The wall plate, *C*, was a channel, $\frac{5}{8}$ by 3 $\frac{1}{4}$ by 1 $\frac{1}{2}$ in., 4 ft 1 in. long, formed from

sheet steel, No. 18 United States Standard Gage (0.049 in. thick before galvanizing). The plate enclosed the upper ends of the panels with a snug fit and the 1 $\frac{1}{2}$ -in. flange was fastened to the panels by screws, one in each panel at mid-width. The primary purpose of the plate is to align the panels during the erection of the building.

Angle.—The angle, *D*, was the same in section as the sill, *B*. In a house the member corresponding to this angle is the support either for a floor or roof and is never identical with angle *D*.




FIGURE 2.—Details of wall specimen AL.

A, panel; *B*, sill; *C*, wall plate; *D*, angle.

Furring strips.—The furring strips, *E*, were pine, 2 $\frac{5}{8}$ by 2 $\frac{5}{8}$ in. (nominal 1 by 3 in.), 4 ft 1 in. long, spaced 1 ft 4 in. on centers. The strips were fastened to the studs by screw nails, one at each stud.

Inside face.—The inside face, *F*, was a one-piece insulating board, 8 ft 0 in. by 4 ft 0 in. by $\frac{3}{4}$ in., fastened to each furring strip by finishing nails. Two nails were used at each of the fasten-

ing points, which were spaced approximately 1 ft 4 in. on centers.

(2) *Eight-Foot Wall Specimens.*—The 8-ft wall specimens were 8 ft 0 in. high, 8 ft 0 in. wide, and 4½ in. thick. The specimens were similar to the 4-ft specimens and each specimen had six “Steelox” panels and two insulating boards, each 8 ft 0 in. by 4 ft 0 in. by ¾ in. The joint between the boards was vertical.

(c) Comments

The standard width of “Steelox” wall panels is 1 ft 4 in., but panels having other widths can be supplied.

When erecting the building, the sill with its felt strip is fastened to the foundation by ex-




FIGURE 3.—Wall specimen AL-C3 under compressive load.




FIGURE 4.—Compressive load on wall AL.

Load-shortening and load-set results for specimens AL-C1, C2, and C3. For the compressive load the thickness of the specimens was taken as 3 in., that of the structural portion. The load was applied 2 in. from the outside face. The loads are in kips per foot of actual width of specimen. The shortenings and sets are for a height of 8 ft. They were computed from the values obtained from the compressometer readings. The gage length of the compressometers was 7 ft 6 in.

pansion or anchor bolts, and at one corner of the building a corner panel is fastened to the sill by hook bolts. Starting at the corner, the wall panels are interlocked with the corner panel and with each other and fastened to the sill by hook bolts. The flanged sides of the panels are covered with blue-lead paint before assembly. Shorter panels are used at window openings. The inside of the sill is covered with asphalt, ½ in. deep, and the inside of the assembled steel is covered with asphalt emulsion.

Openings for standard door and window frames are framed with sill and lintel angles, fastened by hook bolts. Through-the-wall flashing is used over the top of the frames and sealed with asphalt between the lintel angles and the wall panels.

The wall panels may be further insulated by rock-wool batts placed between the studs after erection. When so insulated the sill is not covered with asphalt.

2. COMPRESSIVE LOAD

Wall specimen *AL-C3* under compressive load is shown in figure 3. The results for wall specimens *AL-C1*, *C2*, and *C3* are shown in table 9 and in figures 4 and 5.

TABLE 9.—Structural properties of wall *AL*

[Weight, 4.96 lb/ft²]

Load	Load applied	Specimen designation	Failure of loaded face, height of drop	Failure of opposite face, height of drop	Maximum height of drop	Maximum load
Compressive	2 in. from outside face.*	<i>C1</i>	ft	ft	ft	kips/ft
		<i>C2</i>				6.50
		<i>C3</i>				6.32
	Average					6.34
						6.39
Transverse	Inside face; span, 7 ft 6 in.	<i>T1</i>				lb/ft ²
		<i>T2</i>				144
		<i>T3</i>				164
	Average					151
						153
Transverse	Outside face; span, 7 ft 6 in.	<i>T4</i>				135
		<i>T5</i>				138
		<i>T6</i>				134
	Average					136
						136
Concentrated	Inside face	<i>P1</i>				lb
		<i>P2</i>				250
		<i>P3</i>				250
	Average					265
						255
Concentrated	Outside face	<i>P4</i>				300
		<i>P5</i>				400
		<i>P6</i>				375
	Average					358
						358
Impact	Inside face; span, 7 ft 6 in.	<i>I1</i>	6.5	7.0	7.5	
		<i>I2</i>	4.0	6.0	7.0	
		<i>I3</i>	5.5	6.5	9.5	
	Average		5.3	6.5	8.0	
Impact	Outside face; span, 7 ft 6 in.	<i>I4</i>	4.0	7.5	9.0	
		<i>I5</i>	3.0	7.0	9.0	
		<i>I6</i>	3.5	8.0	9.0	
	Average		3.5	7.5	9.0	
Racking	Upper end	<i>R1</i>				kips/ft
		<i>R2</i>				0.552
		<i>R3</i>				.610
	Average					.635
						.599

* For the compressive load, the thickness of the specimens was taken as 3 in., that of the structural portion only.

Specimens *C1* and *C3* failed by buckling of the outside faces at the lower ends of the specimens. Specimen *C2* failed by buckling of the outside face and studs at two-thirds of the height above the lower end.




FIGURE 5.—Compressive load on wall *AL*.

Load-lateral deflection and load-lateral set results for specimens *AL-C1*, *C2*, and *C3*. For the compressive load the thickness of the specimens was taken as 3 in., that of the structural portion. The load was applied 2 in. from the outside face. The loads are in kips per foot of actual width of specimen. The deflections and sets are for a gage length of 7 ft 6 in., the gage length of the deflectometers.

3. TRANSVERSE LOAD

The results are shown in table 9 and in figure 6 for wall specimens *AL-T1*, *T2*, and *T3*, loaded on the inside face, and in figure 7 for wall specimens *AL-T4*, *T5*, and *T6*, loaded on the outside face.

Each of the specimens *T1*, *T2*, and *T3* failed by buckling of the studs under one of the loading rollers.

Specimens *T4* and *T6* failed by buckling of both the studs and the outside (loaded) faces between the loading rollers. Specimen *T5* failed by buckling of the studs at one of the loading rollers and buckling of the outside face between the loading rollers.

4. CONCENTRATED LOAD

The results are shown in table 9 and in figure 8 for wall specimens *AL-P1*, *P2*, and *P3*, loaded on the inside face, and in figure 9 for specimens *AL-P4*, *P5*, and *P6*, loaded on the outside face.




FIGURE 6.—Transverse load on wall AL, load applied to inside face.

Load-deflection and load-set results for specimens AL-T1, T2, and T3 on the span 7 ft 6 in.




FIGURE 8.—Concentrated load on wall AL, load applied to inside face.

Load-indentation results for specimens AL-P1, P2, and P3.




FIGURE 7.—Transverse load on wall AL, load applied to outside face.

Load-deflection and load-set results for specimens AL-T4, T5, and T6 on the span 7 ft 6 in.




FIGURE 9.—Concentrated load on wall AL, load applied to outside face.

Load-indentation results for specimens AL-P4, P5, and P6.

Each of the specimens *P1*, *P2*, and *P3* failed by punching of the disk through the loaded face of the specimen.

For specimens *P4*, *P5*, and *P6*, the indentations were 0.81, 0.96, and 1.90 in. after loads of 300, 400, and 375 lb, respectively. Loads greater than these were not applied because the loaded faces of the specimens deformed so that they interfered with the dynamometer.

5. IMPACT LOAD

The results are shown in table 9 and in figure 10 for wall specimens *AL-I1*, *I2*, and *I3*, loaded on the inside face, and in figure 11 for wall specimens *AL-I4*, *I5*, and *I6*, loaded on the outside face.

Specimen *I1* failed by cracking of the inside (loaded) face across the entire width of the specimen at midspan and buckling of the studs near the middle of the specimen. Specimens *I2* and *I3* failed by rupture of the inside (loaded) face and the furring strips at the middle of the specimens, buckling of the outside faeces and studs, and opening of the panel joints.




FIGURE 10.—Impact load on wall *AL*, load applied to inside face.

Height of drop-deflection and height of drop-set results for specimens *AL-I1*, *I2*, and *I3* on the span 7 ft 6 in.




FIGURE 11.—Impact load on wall *AL*, load applied to outside face.

Height of drop-deflection and height of drop-set results for specimens *AL-I4*, *I5*, and *I6* on the span 7 ft 6 in.

Specimens *I4*, *I5*, and *I6* failed by opening of the panel joints, followed by buckling of the studs and the outside (loaded) faces at the middle of the specimens, and rupture of the inside faces.



FIGURE 12.—Wall specimen *AL-R3* under racking load.




FIGURE 13.—Racking load on wall AL.

Load-deformation and load-set results for specimens AL-R1, R2, and R3. The loads are in kips per foot of actual width of specimen. The deformations and sets are for a height of 8 ft. They were computed from the values obtained from the measuring-device readings. The gage length of the measuring device was 6 ft.

6. RACKING LOAD

Wall specimen AL-R3 under racking load is shown in figure 12. The results for wall specimens AL-R1, R2, and R3 are shown in table 9 and in figure 13.

Each of the specimens failed by buckling of the outside faces of the panels at both the upper and lower ends of the specimens and opening of the panel joints. A few screws fastening the wall plates to the upper ends of the specimens sheared.

V. PARTITION AM

1. SPONSOR'S STATEMENT

(a) Materials

Insulating board.—Wood-fiber. Insulite Co.'s "Graylite Building Board."

Wood.—Pine, shortleaf, yellow, No. 1 common, finished four sides.

Nails.

Finishing, 6d, 2 in. long.

Common, 16d, 3½ in. long.

Paint.

Casein, priming. United States Gypsum Co.'s "K-Cemo."

Casein, finish. United States Gypsum Co.'s "Texolite."

(b) Description

The partition specimens were 8 ft 0 in. high, 4 ft 0 in. wide, and 4½ in. thick. Each specimen consisted of two insulating-board faces, A, as shown in figure 14, fastened to wood framing by nails. The wood framing consisted of two studs, B, and two half studs, C, fastened to a soleplate, D, and a top plate, E, by nails. Both faces were covered with one coat of priming paint and one coat of finish paint.

The price of this construction was \$0.17/ft².

Faces.—The faces, A, were one-piece insulating boards, 8 ft 0 in. by 4 ft 0 in. by ½ in., fastened to the wood framing by finishing nails, spaced 1 ft 4 in. along each stud and half stud.

Studs.—The studs, B, were pine, 1½ by 3½ in. (nominal 2 by 4 in.), 7 ft 8¼ in. long.

Half studs.—The half studs, C, were pine, 2½ by 3½ in. (nominal 1 by 4 in.), 7 ft 8¼ in. long.

Soleplate and top plate.—Both plates, D and E, were pine, 1½ by 3½ in. (nominal 2 by 4 in.), 4 ft 0 in. long. The plates were fastened to the studs and half studs by common nails, two at each end of the studs.




FIGURE 14.—Partition specimen AM.

A, face; B, stud; C, half stud; D, soleplate; E, top plate.

2. IMPACT LOAD

The results for partition specimens *AM-I1*, *I2*, and *I3* are shown in table 10 and in figure 15.

TABLE 10.—Structural properties of partition *AM*

[Weight, 3.04 lb/ft²]

Load	Load applied	Specimen designation	Failure of loaded face, height of drop	Failure of opposite face, height of drop	Maximum height of drop	Maximum load
Impact	One face; span 7 ft 6 in.	<i>I1</i>	1.0	1.5	1.5	-----
		<i>I2</i>	1.0	1.5	1.5	-----
		<i>I3</i>	1.0	1.5	1.5	-----
		Average	1.0	1.5	1.5	-----
Concentrated	One face	<i>P1</i>	-----	-----	-----	145
		<i>P2</i>	-----	-----	-----	147
		<i>P3</i>	-----	-----	-----	150
		Average	-----	-----	-----	147

Each of the specimens failed by rupture of the loaded face at a drop of 1 ft and rupture of the opposite face at a drop of 1.5 ft.




FIGURE 15.—Impact load on partition *AM*.
Height of drop-deflection and height of drop-set results for specimens *AM-I1*, *I2*, and *I3* on the span 7 ft 6 in.




FIGURE 16.—Partition specimen *AM-P1* under concentrated load.

3. CONCENTRATED LOAD

Partition specimen *AM-P1* under concentrated load is shown in figure 16. The results for partition specimens *AM-P1*, *P2*, and *P3* are shown in table 10 and in figure 17.




FIGURE 17.—Concentrated load on partition *AM*.
Load-indentation results for specimens *AM-P1*, *P2*, and *P3*.

Each of the specimens failed by punching of the disk through the loaded face of the specimen.

VI. FLOOR AN

1. SPONSOR'S STATEMENT

(a) Materials

Steel.

Black sheets, hot-rolled, stretcher-leveled, and resquared. The chemical composition of the steel is given in table 2 and the average mechanical properties in table 3. American Rolling Mill Co.'s "Armco."

Galvanized sheets, hot-rolled. The chemical composition of the steel is given in table 2 and the average mechanical properties in table 3. The sheets were galvanized with Prime Western zinc complying with ASTM Standard B6-37 and having a maximum of 1.60 percent of lead and 0.08 percent of iron. The weight of the zinc coating was 1.75 to 2.00 oz/ft². American Rolling Mill Co.'s "Armco."

Bolts.—Stove, $\frac{1}{4}$ -in. diam, 20 threads per in., $\frac{1}{2}$ in. long, round head, made from SAE 1010 steel, not heat-treated, and plated with cadmium not less than 0.0002 in. thick. Lamson & Sessions Co.

Paint.—Oil, priming, blue lead. The formula is given in table 6. Armstrong Paint and Varnish Works' "No. 1506."

Asphalt emulsion.—Brushing consistency. The formula is given in table 4. Armstrong Paint and Varnish Works' "XA-1696."

Wood.

Oak, red, plain, clear, tongue-and-grooved, end-matched.

Pine, shortleaf, yellow, No. 1 common, finished four sides.

Screw nails.—Heavy-duty, $1\frac{1}{2}$ in. long, No. 6, 8 threads per in., quadruple thread, flat head, needle point, made from SAE 1315 (high side) steel, water-quenched from 1,750° F, and plated with cadmium about 0.0001 in. thick. Hillwood Manufacturing Co.'s "Helyx Drive Screw Nails."

Flooring nails.—5d, cement coated.

(b) Description

The floor specimens were 14 ft 6 in. long, 4 ft 0 in. wide, and $5\frac{5}{16}$ in. thick. Each specimen

consisted of four interlocked sheet-steel "Steelex" panels, *A*, as shown in figure 18, fastened to sheet-steel end members, *B*, by bolts. The panels formed the lower face and joists. The panels were covered with one coat of paint applied by spraying. The sides of the flanges of the panels which were in contact after assembly were covered with paint applied with a brush before assembly. The inside of the assembled panels was covered with one coat of asphalt emulsion applied with a brush after assembly. Wood sleepers, *C*, were fastened to the joists by screw nails and a wood-finish floor, *D*, was fastened to the sleepers by flooring nails.

The price of this construction was \$0.48/ft².

Panels.—The panels, *A*, were channels, 1 ft




FIGURE 18.—Floor specimen AN.

A, panel; *B*, end member; *C*, sleeper; *D*, finish floor.

0 in. by 4 in., 14 ft $5\frac{25}{32}$ in. long, formed from black sheet steel, No. 18 United States Standard Gage (0.049 in. thick). The edges of the flanges of each panel were formed to interlock with the flanges of adjacent panels. The flanges when interlocked formed joists of two thicknesses of steel, integral with the lower face.

End members.—The end members, *B*, were angles, $6\frac{5}{8}$ by $2\frac{3}{4}$ in., 4 ft 1 in. long, formed from galvanized sheet steel, No. 12 United States Standard Gage (0.1072 in. thick before galvanizing). The horizontal $6\frac{5}{8}$ -in. legs were fastened to the panels by bolts, spaced 4 in. on centers. The vertical legs had $\frac{3}{8}$ -in. diam holes, spaced 1 ft 4 in. on centers, for hook-bolt connections to the sill.

Sleepers.—The sleepers, *C*, were pine, $2\frac{5}{8}$ by $2\frac{5}{8}$ in. (nominal 1 by 3 in.), 14 ft 6 in. long,

fastened to the joists by screw nails, spaced about 1 ft 6 in. on centers.

Finish floor.—The finish floor, *D*, was oak, $2\frac{5}{32}$ by $2\frac{1}{4}$ in. (nominal $1\frac{3}{16}$ by $2\frac{1}{4}$ in.), fastened to the sleepers by blind nailing with flooring nails, one at each sleeper.

(c) Comments

The standard width of "Steelox" floor panels is 1 ft 0 in., but panels having other widths can be supplied.

In the building, the end members to which the floor panels are fastened rest on part of the felt strip under the sill. The vertical legs of the end members are fastened to the studs of the wall panels and to the sill by hook bolts, one at each stud.

The finish floor may be yellow pine, oak, or maple. The lower faces of the floor panels form the ceiling when there is a room below and may be finished with paint or wallpaper.

2. TRANSVERSE LOAD

The results for floor specimens *AN-T1*, *T2*, and *T3* are shown in table 11 and in figure 19.

TABLE 11.—*Structural properties of floor AN*

[Weight, 8.03 lb/ft²]

Load	Load applied	Specimen designation	Maximum height of drop	Maximum load
Transverse.....	{ Upper face; span 12 ft 0 in.	<i>T1</i>	ft	lb/ft ²
		<i>T2</i>		189
		<i>T3</i>		193
		Average.....		188
Concentrated...	Upper face.....	<i>P1</i>		lb
		<i>P2</i>		^a 1,000
		<i>P3</i>		^a 1,000
		Average.....		^a 1,000
Impact.....	{ Upper face; span 12 ft 0 in.	<i>I1</i>	^a 10.0	
		<i>I2</i>	^a 10.0	
		<i>I3</i>	^a 10.0	
		Average.....	^a 10.0	

^a Specimen did not fail.

Each of the specimens failed by buckling of the joists at or between the loading rollers and transverse movement of the finish floor with respect to the lower face. The angle between the joists and the lower face, originally 90°, decreased to about 70°.




FIGURE 19.—*Transverse load on floor AN.*
Load-deflection and load-set results for specimens *AN-T1*, *T2*, and *T3* on the span 12 ft 0 in.

3. CONCENTRATED LOAD

The results for floor specimens *AN-P1*, *P2*, and *P3* are shown in table 11 and in figure 20.




FIGURE 20.—*Concentrated load on floor AN.*
Load-indentation results for specimens *AN-P1*, *P2*, and *P3*.




FIGURE 21.—Floor specimen AN-11 during the impact test.

The indentations after a load of 1,000 lb had been applied were 0.010, 0.010, and 0.006 in. for specimens *P1*, *P2*, and *P3*, respectively, and no other effect was observed.

4. IMPACT LOAD

Floor specimen AN-11 during the impact test is shown in figure 21. The results for floor

specimens AN-11, 12, and 13 are shown in table 11 and in figure 22.

The sets after a drop of 10 ft were 0.016, 0.007, and 0.006 in. for specimens 11, 12, and 13, respectively, and no other effect was observed.

VII. ROOF A0

1. SPONSOR'S STATEMENT

(a) Materials

Steel.—Hot-rolled sheets, hot-dip galvanized and prepared for paint by the "Paint Grip" process. The chemical composition of the steel is given in table 2 and the average mechanical properties in table 3. American Rolling Mill Co.'s "Armco."

The sheets were galvanized with Prime Western zinc complying with ASTM Standard B6-37 and having a maximum of 1.60 percent of lead and 0.08 percent of iron. The weight of the zinc coating was 1.25 to 1.50 oz/ft² for the 20-gage sheets and 1.75 to 2.00 oz/ft² for the 12-gage sheets.

The galvanized sheets were prepared for paint by the "Paint Grip" process according to the following specification:

"All galvanized sheets and members shall be phosphated by immersion in a solution containing free phosphoric acid, an oxidizing agent (nitrate), and iron and zinc phosphate. After this treatment the articles shall be thoroughly rinsed in clear water."




FIGURE 22.—Impact load on floor AN.

Height of drop-deflection and height of drop-set results for specimens AN-11, 12, and 13 on the span 12 ft 0 in.

Bolts.—Stove, $\frac{1}{4}$ -in. diam, 20 threads per in., $\frac{1}{2}$ in. long, round head, made from SAE 1010 steel, not heat-treated, and plated with cadmium not less than 0.0002 in. thick. Lamson & Sessions Co.

Asphalt emulsion.—Brushing consistency. The formula is given in table 4. Armstrong Paint and Varnish Works' "XA-1696."

Wood.—Pine, shortleaf, yellow, No. 1 common, finished four sides.

Screw nails.—Heavy-duty, $1\frac{1}{2}$ in. long, No. 6, 8 threads per in., quadruple thread, flat head, needle point, made from SAE 1315 (high side) steel, water-quenched from 1,750° F, and plated with cadmium about 0.0001 in. thick. Hillwood Manufacturing Co.'s "Helyx Drive Screw Nails."

Insulating board.—Wood-fiber, $\frac{3}{4}$ in. thick. Insulite Co.'s "Bildrite Sheathing."

Box nails.—4d, $1\frac{1}{2}$ in. long.

Roofing felt.—Rag base, saturated with asphalt. Logan-Long Co.

Asphalt.—Softening point 180° F. Logan-Long Co.

Paint.

Oil, priming, blue lead. The formula is given in table 6. Armstrong Paint and Varnish Works' "No. 1506."

Casein, finish. United States Gypsum Co.'s "Texolite."

(b) Description

The roof specimens were 14 ft 6 in. long, 4 ft 0 in. wide, and $4\frac{7}{8}$ in. thick. Each specimen consisted of three interlocked sheet-steel "Steelex" panels, *A*, as shown in figure 23, fastened to sheet-steel end members, *B*, by bolts. The panels formed the lower face and joists. The sides of the flanges of the panels which were in contact after assembly were covered with oil paint applied with a brush before assembly. The inside of the assembled panels was covered with one coat of asphalt emulsion applied with a brush. Wood furring strips, *C*, were fastened to the joists by screw nails, and insulation, *D*, was fastened to the furring strips by box nails. The insulation was covered by a built-up roofing, *E*, laid in asphalt. The lower face of the specimen was covered with casein paint.




FIGURE 23.—Roof specimen AO.

A, panel; *B*, end member; *C*, furring strip; *D*, insulation; *E*, built-up roofing.

The price of this construction was \$0.52/ft².

Panels.—The panels, *A*, were channels, 1 ft 4 in. by 3 in., 14 ft 5 $\frac{1}{2}$ in. long, formed from stretcher-leveled and resquared sheet-steel, No. 20 United States Standard Gage (0.0368 in. thick before galvanizing). The edges of the flanges of each panel were formed to interlock with the flanges of adjacent panels. The flanges when interlocked formed joists of two thicknesses of steel, integral with the lower face.

End members.—The end members, *B*, were zees, 1 by 2 $\frac{1}{4}$ by 2 $\frac{1}{8}$ in., 4 ft 1 in. long, formed from sheet steel, No. 12 United States Standard Gage (0.1072 in. thick before galvanizing). The vertical webs had slots, 2 by $\frac{7}{16}$ in., spaced 1 ft 4 in. on centers, for hook-bolt connections to wall panels. The 2 $\frac{1}{8}$ -in. flanges were fastened to the panels by bolts, spaced 8 in. on centers.

Furring strips.—The furring strips, *C*, were pine, 2 $\frac{5}{8}$ by 2 $\frac{5}{8}$ in. (nominal 1 by 3 in.), 4 ft 1 in. long, spaced about 1 ft 6 in. on centers, and fastened to the joists by screw nails, one at each joist.

Insulation.—The insulation, *D*, was insulating board, $\frac{3}{4}$ in. thick, fastened to the furring strips by box nails, spaced about 1 ft 4 in. on centers.

Built-up roofing.—The built-up roofing, *E*, consisted of three plies of roofing felt, each laid in and covered with asphalt applied by mopping. There was one 30 lb/108² ft ply and two 15 lb/108 ft² plies.

(c) Comments

For flat roofs, the roof panels are supported by the end members which are fastened to the studs of the wall panels by hook bolts, one at each stud, the upper flanges of the end members fitting into slots cut in the studs. The insulation and built-up roofing cover the inside of the parapet formed by the wall extending above the roof line. A sheet-steel coping covers the top of the parapet and the edge of the roofing. If there is no parapet, a galvanized cross flashing under the roofing is formed by the apron of the sheet-metal hanging gutter. The lower faces of the roof panels form the ceiling of the room below and may be finished with paint or wallpaper.

For sloping roofs, the steel panels are similar to those for flat roofs, but no insulation or built-up roofing is applied over them. The panels are supported at the eaves by a formed sheet-steel section which rests on the wall plate and is fastened to the studs by hook bolts. The roof panels are fastened with S-shaped sheet-steel clips. The panels are connected to the ridge by a built-up sheet-steel ridge member with flanges on which the panels bear. These flanges are covered with 65-lb roofing felt. Over this is applied calking material into which the panels are embedded. The portions of the roof panels that are in contact after assembly are painted with blue-lead paint before assembly. A sheet-steel ridge cap covers the ridge and is fastened to the roof panels by screws. The upper face of the roof is covered with two coats of roofing paint. The lower face is covered with one coat of asphalt emulsion.

For sloping roofs, the ceiling joists are wood, supported by a flange of the sheet-steel member which supports the roof panels, and fastened to it by nails passing through holes in the flange. Insulating board, $\frac{3}{4}$ in. thick, is fastened by nails to the top of the joists and $\frac{1}{2}$ -in. insulating board to the bottom. Loose rock-wool insulation is used between the joists around the perimeter of the building. The lower board forms the ceiling and may be finished with paint.

2. TRANSVERSE LOAD

Roof specimen *AO-T2* under transverse load is shown in figure 24. The results for roof




FIGURE 24.—Roof specimen *AO-T2* under transverse load.

specimens *AO-T1*, *T2*, and *T3* are shown in table 12 and in figure 25.

TABLE 12.—Structural properties of roof *AO*
[Weight, 6.99 lb/ft²]

Load	Load applied	Specimen designation	Maximum load
Transverse.....	Upper face; span 14 ft 0 in..	<i>T1</i>	lb/ft ² 57
		<i>T2</i>	56
		<i>T3</i>	57
	Average.....		57
Concentrated.....	Upper face.....	<i>P1</i>	lb 445
		<i>P2</i>	425
		<i>P3</i>	455
	Average.....		442




FIGURE 25.—Transverse load on roof *AO*.
Load-deflection and load-set results for specimens *AO-T1*, *T2*, and *T3* on the span 14 ft 0 in.

Specimens *T1* and *T2* failed by buckling of the joists near midspan. Specimen *T3* failed by buckling of the joists under one of the loading rollers.

3. CONCENTRATED LOAD

The results for roof specimens *A0-P1*, *P2*, and *P3* are shown in table 12 and in figure 26.




FIGURE 26.—Concentrated load on roof *A0*.
Load-indentation results for specimens *A0-P1*, *P2*, and *P3*.

Each of the specimens failed by punching of the disk through the built-up roofing and insulation.

VIII. ADDITIONAL COMMENTS
BY SPONSOR

APPROXIMATELY 350 houses using these constructions were completed or under construction July 1, 1938.

The foundations for these houses were either concrete walls or concrete slabs. The chimneys were 4-in. brick walls with clay-tile flue linings, supported on the masonry foundations.


The sponsor supplied the information contained in the sponsor's statement. The description and drawings of the specimens were prepared by E. J. Schell and G. W. Shaw of the Bureau's Building Practice and Specifications Section, under the supervision of V. B. Phelan, from this information and from the specimens themselves. That Section also cooperated in the preparation of the report.

The experimental data were obtained from tests made by the Engineering Mechanics Section, under the supervision of H. L. Whittemore and A. H. Stang, with the assistance of the following members of the professional staff: F. Cardile, R. C. Carter, H. Dollar, M. Dubin, A. H. Easton, A. S. Endler, C. D. Johnson, A. J. Sussman and L. R. Sweetman.

IX. SELECTED REFERENCES

Architectural Record **78**, No. 2, 125 (1935).
Architectural Forum **63**, 567 (1935).
American Architect **149**, No. 2649, 39 (1936).
WASHINGTON, August 4, 1938.

○



The *National Bureau of Standards* was established by act of Congress, approved March 3, 1901, continuing the duties of the old Office of Standard Weights and Measures of the United States Coast and Geodetic Survey. In addition, new scientific functions were assigned to the new Bureau. Originally under the Treasury Department, the Bureau was transferred in 1903 to the Department of Commerce and Labor (now the United States Department of Commerce). It is charged with the development, construction, custody, and maintenance of reference and working standards, and their inter-comparison, improvement, and application in science, engineering, industry, and commerce.

SUBJECTS OF BUREAU ACTIVITIES

Electricity

Resistance Measurements
Inductance and Capacitance
Electrical Instruments
Magnetic Measurements
Photometry
Radio
Underground Corrosion
Electrochemistry
Telephone Standards

Weights and Measures

Length
Mass
Time
Capacity and Density
Gas Measuring Instruments
Thermal Expansivity, Dental
Materials, and Identification
Weights and Measures Laws
and Administration.
Large-Capacity Scale Testing
Limit Gages

Heat and Power

Thermometry
Pyrometry
Heat Measurements
Heat Transfer
Cryogenics
Fire Resistance
Automotive Power Plants
Lubrication and Liquid Fuels

Optics

Spectroscopy
Polarimetry
Colorimetry and Spectropho-
tometry
Optical Instruments
Radiometry
Atomic Physics, Radium, and
X-Rays
Photographic Technology
Interferometry

Chemistry

Paints, Varnishes, and Bitu-
minous Materials
Detergents, Cements, Corro-
sion, Etc.

Chemistry—Continued

Organic Chemistry
Metal and Ore Analysis, and
Standard Samples
Reagents and Platinum Metals
Electrochemistry (Plating)
Gas Chemistry
Physical Chemistry
Thermochemistry and Con-
stitution of Petroleum

Mechanics and Sound

Engineering Instruments and
Mechanical Appliances
Sound
Aeronautic Instruments
Aerodynamics
Engineering Mechanics
Hydraulics

Organic and Fibrous Materials

Rubber
Textiles
Paper
Leather
Testing and Specifications
Fiber Structure
Organic Plastics

Metallurgy

Optical Metallurgy
Thermal Metallurgy
Mechanical Metallurgy
Chemical Metallurgy
Experimental Foundry

Clay and Silicate Products

Whiteware
Glass
Refractories
Enameled Metals
Heavy Clay Products
Cement and Concreting
Materials
Masonry Construction
Lime and Gypsum
Stone

Simplified Practice

Wood, Textiles, and Paper
Metal Products and Construc-
tion Materials
Containers and Miscellaneous
Products
Materials-Handling Equip-
ment and Ceramics

Trade Standards

Wood, Wood Products, Paper,
Leather, and Rubber
Metal Products
Textiles
Apparel
Petroleum, Chemical, and Mis-
cellaneous Products

Codes and Specifications

Safety Codes
Building Codes
Building Practice and Specifi-
cations
Producer Contacts and Certi-
fication
Consumer Contacts and
Labeling

Office

Finance
Personnel
Purchase and Stores
Property and Transportation
Mail and Files
Library
Information

Shops

Instrument
Woodworking
Glassblowing
Construction Stores and Tool
Room

Operation of Plant

Power Plant
Electrical
Piping
Grounds
Construction
Guard
Janitorial

